MAHATMA GANDHI UNIVERSITY

ANRF - PAIR Project

P.D. Hills P.O. Kottayam, Kerala – 686 560, Email: anrfpair@mgu.ac.in

MGU/ANRF-PAIR/Short-Tender/01/2025-26 **Dated: 12.01.2026**

SHORT-TENDER NOTICE

The Principal Investigator, ANRF-PAIR Project, Mahatma Gandhi University, Kottayam invites **sealed competitive Tenders from reputed firms for the interior work of the ANRF-PAIR Project Office as per the specifications mentioned below.**

The sealed covers containing Tender details are super scribed "Tender for the interior work of ANRF PAIR project office" **and send to ANRF PAIR project, Room no-417, 3rd floor, Convergence Academia Complex, Mahatma Gandhi University, Kottayam, Kerala. Pin: 686560p**

Last Date of Receiving Tenders: 19.01.2026, Time : 3.00PM

Opening date of Tenders: 21.01.2026, Time: 10 AM

SPECIFICATIONS

Technical Specification for the interior work of ANRF PAIR project office at convergence academia complex.

SL NO	PARTICULERS	QTY	UNIT
1	**Double skin Partition**	3	NOS
	Maerial using aluminium framework with both side plywood with lamination. Providing 10mm Glass over the partition with Table partition clamp.		
2	**Conference Hall Chair**	18	NOS
	Material using High back chair - Model name Material using ABS mesh type back with lumbar support and hollowed seat for airflow PU Moulded upolsterated with soft touch fabric. Hand rest using PU material. 24"		

Scanned with OKEN Scanner

	Nylon base Base with 50mm castor wheel. Providing class 4 gas lift technology. Included most advanced synchro 1 Mechanism.		
3	**Conference Hall Aluminium Partition**	32	SQM
	Material using frame work using 50x25MM Aluminium section, with one side 9/12MM Plywood with texture finish lamination with 1mm thick. Hardware as per design.		
4	**Wash counter including Tap pipe work etc**	1	NOS
	Material using WPC/Multiwood without lamination - including hardware like hinges, bush, handle etc. Providing Table top wash basin, Tap, Waste cupling pipe work etc.		
5	**Painting - Putty, Primer, Emulsion**	160	SQM
	Providng 1 cot primer, 2 cot putty, 2 cot emulsion on ceiling and wall area.		

Terms & Conditions:

1. Tender form can be downloaded from the official web site of Mahatma Gandhi University (https://www.mgu.ac.in/uploads/2020/08/Tender-Form.pdf?x99264) and **Tender form rate-0.2% of quoted amount (Lowest amount = Rs. 400/- +GST, Maximum amount = Rs. 1500/- +GST)** can be paid by online in the University online payment system and challan should be attached along with the Tender.
2. Tender Amount should be including all taxes.
3. Tenure of Tender should be three months.
4. A preliminary agreement in document paper of Rs. 200/- has to be submitted along with the tender.
5. **Ernest Money Deposit (EMD) calculated @ 1% of (quoted amount) the Purchase assessment cost (PAC)** should be paid by through University online payment (www.mgu.ac.in.online payment - miscellaneous) or Demand Draft in favour of The Principal Investigator, ANRF-PAIR Project, Mahatma Gandhi

Scanned with OKEN Scanner

University, Kottayam and submitted along with the sealed tender.

6. An agreement must be submitted by the qualified bidder and should submit 5% of the PAC as security deposit.
7. Tenders received after the last date and time should be rejected. The Registrar has the right to accept or reject the tender without any reason. If the tender opening day is a holiday it will open in the next office working day.
8. If not received the minimum number tenders, the last date will be extended to the next 15 days.
9. If received more tenders during the extended period, the first received tenders also to be considered.
10. Final payment should be released only after the completion of work.

P.D Hills
12-01-2026

Dr. Radhakrishnan E K
Principal Investigator
ANRF PAIR Project
M G University

Dr. RADHAKRISHNAN E. K.
Principal Investigator
ANRF - PAIR Project
Mahatma Gandhi University
P.D. Hills (P.O.), Kottayam, Kerala - 686 560
Ph: +91 9847901149

Scanned with OKEN Scanner